



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

2512

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

क्रमांक: 7751/M-10/2021

दिनांक: 28/08

**QUOTATION NOTICE**

To,

M/s.....

The sealed quotations are invited for P/L old C.C pavers blocks and other misc. work at backside of mess at new C.V. hostel. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 04/09/2021

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling of old door / windows chaukhats with hold fast & including stacking of dismantled material directed by the engineer incharge.	2.10	Sqm.	
2.	P/f 1mm thick M.S sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junction and corners all necessary fittings complete using M.S. flats 30x6mm for diagonol braces and central cross piece.	1.75	Sqm.	
3.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.65	Cum.	
4.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	6.35	Sqm.	
5.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	4.65	Cum.	
6.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	3.16	Sqm.	
7.	P/L vitrified floor tiles in 600x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	1.95	Sqm.	
8.	P/L Vitrified wall tiles 300x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	7.74	Sqm.	
9.	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of E/I.	64.62	Sqm.	
10.	P/L 40mm thick Cement concrete flooring in 1:2:4 cement , coarse sand & 20mm stone grit with 3mm thick floating coat of neat cement and curing complete including of form work.	15.39	Sqm.	
11.	Applying one coat of water thinable cement primer of approved brand on new wall surface.	31.20	Sqm.	

JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu

दिनांक 23/08/21


12.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	3.16	Sqm.	
13.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	57.64	Sqm.	
14.	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	7.69	Sqm.	
15.	S/F of white glazed Orissa Pan 580 mm dia with hepco red C.I traps 100mm dia.	01	No.	
16.	White glazed earthen ware (European type) W.C pan 505mm dia with seat cover of jaguar ESSCO, cera, hindware.	01	No.	
17.	S/F PVC bib cock 15mm dia make of prayag.	01	No.	
18.	S/F of C.P brass short body bib cock 15mm dia. Make of hindware, cera or equivalent.	01	No.	
19.	Providing welder with welding machine for fabrication.	01	No.	
20.	Providing labour for cleaning of site, collecting & disposal of malwa.	04	Nos.	


Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


No-7752-7756/M-10/2021


  
(Dinesh Kumar Raj)  
Executive Engineer


No...../ of DT. 

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 28/08/2021  
i. To A.H.A. 9/30/21
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.

  
Suresh Kumar  
A.E.

  
(Dinesh Kumar Raj)  
Executive Engineer

  
Suresh Kumar  
A.E.