किंगजार्जचिकित्साविश्वविद्यालयउ०प्र०, लखनऊ- 226003
निर्माणविभाग
फोन (कुलसचिव कार्यालय) : 0522–2257540 फैक्स: 0522–2257539 वेबसाइट: www.kgmcindia.edu

4664

Information Technology Cell K.G.M.U. Date 21-12-21 Time 3:

पत्रांक: 9952/MMC

दिनांक: 21/12/2021

QUOTATION NOTICE

To,

M/s.....
.....
.....

The sealed quotation are invited Renovation of Superintendent Dental Office Room with toilet at Dental building KGMU Lucknow. from the registered contractor of K.G.M.U. The Detail of quotation can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 28/12/2021 Details of the work as given below-

S.N.	Particular	Quantity	Unit	Rates
1.	Dismantling existing plaster including disposal of refuse as directed by the engineer- in- charge with in a distance of 60mtr (200 ft).	11.81	Sqm	
2.	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 metres lead :Thickness above 25 mm up to 40 mm.	22.69	Sqm	
3.	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	17.67	Sqm	
4.	P/L ceramic wall tiles in size 300x600mm with water absorption less then 0.08% and conferming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	42.01	Sqm	
5.	12mm cement plaster of mix 1:4 (1 cement : 4 coarse sand).	11.81	sqm	
6.	P/L ceramic floor tiles in size 300x300mm with water absorption less then 0.08% and conferming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	3.65	Sqm	
7.	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.	11.81	Sqm	
8.	Providing and applying white cement based putty of average thickness 1mm of approved brand and manufacture, over the new plastered wall surface to prepare the surface even and smooth complete.	11.81	Sqm	
9.	Providing and applying white cement based putty of average thickness 0.60 mm of approved brand and manufacture, over the old plastered wall surface to prepare the surface even and smooth complete.	17.68	Sqm	
10.	Oil bound distemper in two coat	88.39	Sqm	
11.	Enamel painting in two coat.	12.29	Sqm	
12.	Wax polish or approved French polish after rubbing down with sand paper in two coat including supply of all materials, labour and t & P etc required for proper completion of the work	9.45	Sqm	
13.	False ceiling Repair labour material complete etc.	2.84	Sqm	
14.	White glazed earthern ware (European type) W.C pan 505mm	1	Nos	

	diawith seat cover of jaguar ESSCO, cera, hindware.			
15.	S/F 10 lit PVC low down cistern for appd. Quality in complete.	1	Nos	
16.	S/F of wash hand basin heavy quality make of approved brand with pillar cock, bracket pvc connection, waste pipe complete.	1	Nos	
17.	S/F of C.P soap dish of approved quality make sera or equivalent.	1	Nos	
18.	P/F 600x450mm beveled edge mirror of superior glass complete with 6mm thick hard board fixed to wooden cleats with C.P brass screw and washer complete.	1	Nos	
19.	S/F of C.P brass short body bib cock 15mm dia make of hindware, cera or equivalent	1	Nos	
20.	S/F Jet spray with C.P lead 1.5 m for appd. Quality.	1	Nos	
21.	S/F PVC connection 600 mm long prayag make.	1	Nos	
22.	P/F of C.P two way angle valve 15mm dia.	2	Nos	
23.	S/F PVC Waste pipe 32mm dia	1	Nos	
24.	Providing and fixing of GI pipes complete with GI fittings and clamps including cutting and making good the wall etc internal work exposed to wall 20mm dia nominal bore.	5	Rmt	
25.	P/F of CP brass angle valve for basin mixer point of approved quality conforming to IS :8931 15mm normal bore	2	Nos	

Terms & Conditions.

1. G.S.T &LabourCess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours Faithfully

(Dinesh Kumar Raj)
Executive Engineer

No. 7953-58/M/10 Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Superintendent, Dental Deptt, K.G.M.U, U.P. Lucknow
4. Dr. Richakhanna , Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU, Website.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

(Dinesh Kumar Raj)
Executive Engineer