



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 5616 / एम-10 / 2020

दिनांक: 23/11/2020

Quotation Notice

Sub:- Construction of Guard Room at entrance gate of New P.G. Girls Hostel at K.G.M.U., U.P., Lucknow

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 21/12/2020.....


Sl.No	Particular	Qty	Unit.	Rates
1	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T & P etc for proper completion of the work.	3.11	Cum	
2	M-150 class 120mm thick brick work in 1:3 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	10.57	Sqm	
3	P/L P.C.C. 1:6:12 cement, fine sand & 40mm brick ballast.	1.14	Cum	
4	P/L R.C.C. work for slabs in 1:2:4 cement, coarse sand & 20mm stone grit.	1.00	Cum	
5	Mild Steel work for reinforcement in plain cement concrete including binding, bending and cutting complete.	80.70	Kg.	
6	P/L 12mm cement plaster in 1:4 on ceiling with cement and coarse sand including supply of all material labour and T & P etc for proper completion of the work.	4.37	Sqm	
7	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T & P etc for proper completion of the work.	45.85	Sqm	
8	P/L 12mm cement plaster in 1:3 (1 Cement : 3 Coarse Sand) finished with a floating coat of neat cement.	8.74	Sqm	
9	P/L white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	37.37	Sqm	
10	Distemping with oil bound distemper two coat of approved brand on old surface to give an even shade including all material, labour T & P etc complete.	36.37	Sqm	
11	S/f of anodized aluminum partly fixed and partly openable window with aluminum section 4x1-3/4x2" window panel and	0.98	Sqm	

	5mm thick plain glass including all, Labour, Material T & P etc.			
12	Providing labour for cleaning of site.	4.00	Nos.	
13	Mild steel fabrication angle M.S. sheet	78.20	Kg.	

Terms & condition

1. The quotation should be accepted by Registered Contractors of K.G.M.U.U.P., Lucknow.
2. The rates should be quoted excluding G.S.T. & Labour cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.


Your's Faithfully


(Ram Velas Verma)
Executive Engineer

No. 5617-23/M/10 of dt.

Copy for information and necessary action to:

1. Registrar, K.G.M.U, Lucknow.
2. Finance Officer, K.G.M.U, Lucknow.
3. Provost, New Girls P.G. Hostel, K.G.M.U.U.P., Lucknow.
4. Faculty Incharge/Co-Faculty Incharge, works department, K.G.M.U, U.P., Lucknow.
5. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, K.G.M.U. for uploading the quotation Notice in KGMU. UP, Lucknow.
6. Assistant/Junior Engineer, Works deptt. K.G.M.U, Lucknow.
7. Notice Board.


(Ram Velas Verma)
Executive Engineer

रामसजीवन
२४-११-२०२३