



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu

पत्रांक: 5641/M/10

दिनांक: 28/12/2020

### QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited for P/L floor tiles and painting work in backside varandah of works department. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated .....

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Providing and laying Vitrified tiles in floor of size 600x600mm, with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joint.	19.07	Sqm.	
2.	P/L Vitrified wall tiles 300x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	1.69	Sqm.	
3.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	237.16	Sqm.	
4.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	237.16	Sqm.	
5.	Distempering with oil bound distemper two coat of approved brand on old Surface togive an even shade including all material , labour T&P etc. complete.	341.92	Sqm.	
6.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	58.77	Sqm.	
7.	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	32.98	Sqm.	
8.	S/F of appd quality door closer ISI marked.	01	No.	

#### Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)  
Executive Engineer

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.


दिनांक:.....  
28/12/2020


6642-48/MKU  
of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date.....  
i. To 01/11/2021
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.

28/12/2020

  
(Dinesh Kumar Raj)  
Executive Engineer

  
JE Sandeep Kumar  
A.E.