



किंग जार्ज चिकित्सा विश्वविद्यालय उत्तर प्रदेश, लखनऊ कार्यालय अधिशासी अभियन्ता (विद्युत/यांत्रिक)

पत्रांक 436...../ई0ई0(ई./एम.)

Urgent Quotation Notice

दिनांक 05.06.2024

Sub:- Providing of MCCB 630Amp. 4 pole with enclosure in place of defective & burnt out main switch 400Amp. TPN with HRC fuse & light & power plug in Dy. Registrar Chamber in Administration block at KGMU, Lucknow.

Sir,
Sealed quotations are invited here by the reputed firms/electrical contractors for the following items in sealed envelope to the undersigned in the interest of patient care/ institution with in 3 days from the date of calling quotation :-

Sl. No.	Particulars of Work	Qty.	Rate	Amount in Rs.
1.	S/F of 630Amp. MCCB 36KA 4 pole with making connection of incoming & outgoing complete job.	01 No.		
2.	S/F of MCCB enclosure suitable for 630A 4 pole MCCB	01 NO.		
3.	S/F of lugs 95sq.mm. as per ps. no. 504(g)	09 Nos.		
4.	S/F of lugs 50sq.mm. as per ps. no. 504(e)	03 Nos.		
5.	Dismantling charges of burnt out defective 400Amp. TPN main switch with HRC fuse farm existing place & replaced with MCCB 630Amp. 4 pole complete job.	01 Job.		
6.	S/F of 10 Amp. plug point with modular switch & socket as per ps. no. 134c+187c	02 Nos.		
7.	S/F of 20 Amp. power plug with modular switch & socket as per ps. no. 1139A	02 Nos.		
8.	S/W of submain 2 x 4sq.mm. as ps. no. 211c	05 Mtrs.		
G. Total Rs.				

Terms & Conditions:-

- G.S.T. extra as applicable.
- All the works shall be completed within the given time period (as per work order).
- Quantity may be increase or decrease as per requirements at site and payment shall be made accordingly.
- All the works shall be carried out as per PWD specifications.
- Payment shall be made after satisfactory completion of above works through Finance office only.

No.	Particulars of Work	Qty.	Rate	Amount in Rs.
1.	S/F of 630Amp. MCCB 36KA 4 pole with making connection of incoming & outgoing complete job.	01 No.		
2.	S/F of MCCB enclosure suitable for 630A 4 pole MCCB	01 No.		
3.	S/F of lugs 95sq.mm. as per ps. no. 504(g)	09 Nos.		
4.	S/F of lugs 50sq.mm. as per ps. no. 504(e)	03 Nos.		
5.	Dismantling charges of burnt out defective 400Amp. TPN main switch with HRC fuse farm existing place & replaced with MCCB 630Amp. 4 pole complete job.	01 Job.		
6.	S/F of 10 Amp. plug point with modular switch & socket as per ps. no. 134c+187c	02 Nos.		
7.	S/F of 20 Amp. power plug with modular switch & socket as per ps. no. 1139A	02 Nos.		
8.	S/W of submain 2 x 4sq.mm. as ps. no. 211c	05 Mtrs.		

Executive Engineer (E./M.)
K.G.M.U.U.P., LUCKNOW

Terms & Conditions:-

- G.S.T. extra as applicable.
- All the works shall be completed within the given time period (as per work order).
- Quantity may be increase or decrease as per requirements at site and payment shall be made accordingly.
- All the works shall be carried out as per PWD specifications.
- Payment shall be made after satisfactory completion of above works through Finance office only.