

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.



दिनांक: 19/03/2021

पत्रांक: 2297 / एम-10 / 2021

Quotation Notice

To,

M/s.....

.....

.....

.....

The sealed quotation are invited for **Construction of Toilet near Holding Area in Trauma Center Campus at K.G.M.U.U.P, Lko** from the registered contractor of K.G.M.U.U.P., Lucknow. The Detailed of quotation can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated... 25/03/2021

Details of the work as given below:-

Sl.No	Particular	Qty	Unit.	Rates
1	Dismantling of old flooring including base concrete and disposal of Malva complete.	1.70	Sqm	
2	P/L P.C.C. 1:5:10 cement, fine sand and 40mm. brick ballast in foundation	1.75	Cum	
3	Class-150- Brick work 1:4 cement C-Sand in wall for Foundation	0.88	Cum	
4	Class-150 Brick work 23cm thick wall in 1:4 cement and coarse sand	1.98	Cum	
5	Providing and laying damp proof course 40mm thick with cement	1.00	Sqm	
6	RCC work in lintel 1:1 1/2:3 cement C-Sand stone aggregate.	0.04	Cum	
7	Mild Steel work 10/12 mm dia as for reinforced ment	7.00	Kg.	
8	12mm thick plaster 1:4 cement C-Sand in wall.	12.00	Sqm	
9	P/L Vitrified floor tiles in size 600x600mm with water absorption less then 0.08% and conforming to IS:15622 of approved make in all colours and shed, laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc complete.	1.00	Sqm	
10	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less then 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	5.75	Sqm	
11	P/f of M.S. Iron frame work for GI shed and ventilators	40.00	Kg.	
12	Labour charge for repairing of broken interlocking flooring	2.50	Sqm	

As per
Rise

viding and fixing precoated galvanized iron profile sheets (size, pe and pitch of corrugation as approved by Engineer-in-charge) 0mm (+0.05%) total coated thickness with zinc coating 120 grams sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy ner on both side of the sheet and polyester top coat 15-18 microns. et should have protective guard film of 25 microns minimum to id scratches during transporation and should be supplied in single gth upto 12 metre or as desired by Engineer-in-charge. The sheet ll be fixed using self drilling/self tapping screws of size x55mm) with EPDM seal, complete upto any pitch in zontal/vertical or curved surfaces, excluding the cost of purlins, ers and trusses and including cutting to size and shape wherever ired.	2.30	Sqm	
white cement based putty of average thickness 1mm of approved id on new plastered surface to prepare the surface even and smooth plete.	12.00	Sqm	
bound distemper in two coat.	8.00	Sqm	
lication of two coats Apex. Altima paint of Approved Brand on Surface Given an even Shade including supply of all material, ur T&P as required for proper completion of work	10.00	Sqm	
iding & fixing of P.V.C. door including P.V.C. chaukhat of oved brand made of Rajshree doors or equivalent complete.	1.57	Sqm	
iding and fixing white glazed Orrisa Pan 580mm dia with hepc o.I. traps 100mm dia.	1.00	No	
Wash hand basin white glazed 22x16 complete with pillar cock, ket, waste jail, waste pipe, PVC connection etc.	1.00	No	
of P.V.C. Connection 600mm long.	3.00	No	
f P.V.C. Angle Valve 15mm dia Prayag Make.	2.00	No.	
f looking mirror with polish of 600x450mm size with beveled	1.00	No.	
of C.P soap disk of heavy quality	1.00	No.	
of C.P. towel rod (Make of Parryware or equivalent) 650mm Long oved quality	1.00	No.	
f P.V.C. short body bib cock 15mm dia	2.00	Nos.	
iding and fixing G.I. Pipes complete with G.I. fittings and clamps, aking good the wall etc. concealed pipe, including painting with corrosive bitumastic paint, cutting chases and making good the (20mm dia nominal bore).	27.00	Rmt	
iding and fixing Hepco red HC.I pipe including fitting 100mm	12.00	Rmt	


dition

otation should be accepted by Registered Contractors of K.G.M.U.U.P., Lucknow. ates should be quoted excluding G.S.T. & Labour cess.

ork will completed within given time in the work order.

otation should be reached by Registered post upto date mentioned in quotation.

Your's Faithfully



(Ram Velas Verma)
Executive Engineer

