

(687)

(R) - 15/03/21

(Civil Section)
King George's Medical University Uttar Pradesh,
Lucknow.

No. 2179/M-10

of date 12/03/21

To.

QUOTATION NOTICE

M/s.

The sealed quotation are invited for Providing Sanitary Fittings in toilet, Painting, Glass, cleaning of water tank, and Aluminum work New girls P.G. Hostel, R.A.L.C. (COVID-19), C.T.V.S., Medicine O.P.D., Geriatric mental, D.M.S. main building Room, E.N.T. O.P.D., E.N.T. O.T. Urology, at K.G.M.U., U.P, Lucknow. from the registered contractor of K.G.M.U. The Detail of quotation can be seen at website www.kgmciindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 19/03/21

Details of the work as given below-

S.N.	Particular	Quantity	Unit	Rates
1.	Scrapping old white or colored wash etc including disposal of refuse material as directed by Engineer in charge	36.42	Sqm	
2.	P/L of Birla white putty for making good smooth surface.	36.42	Sqm	
3.	Oil bound distemper in two coat.	72.84	Sqm	
4.	Enamel painting in two coat	14.40	Sqm	
5.	5mm thick Glass with Putty complete.	8.91	Sqm	
6.	P/F Anodized aluminum work for doors, windows and ventilators with extruded built up standard tabular section/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia. and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required with rubber/neoprene gasket etc.	32.45	Kg.	
7.	P/F Float glass panes of 5mm thick in aluminum work for doors, windows, ventilators shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per the directions of engineer-in-charge.	2.70	Sqm.	
8.	P/F 4mm thick ACP sheet in aluminum work for doors, windows, ventilators shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge.	3.20	Sqm.	
9.	P/L of 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shades, colour and texture laid over 20mm thick base cement mortar 1:4 (Cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Area of slab over 0.50 Sqm	1.71	Sqm	
10.	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	2.84	Sqm	
11.	Aluminum Door/Partition Repair Labour Charge complete etc.	12.25	Sqm	
12.	S/F of Aluminum sliding Roller	6.00	Nos	
13.	S/F door closer for approved quality godrej are equivalent	3.00	Nos	
14.	P/F of P.V.C. Bib cock 15mm nominal bore 90mm long weighting not less than 93 gms of appd. quality.	9.00	Nos	
15.	P/F of G.I. Union 25mm dia.	1.00	Nos.	
16.	Providing and fixing of P.V.C. waste pipe 32mm for wash basin/sink	11.00	Nos	
17.	Providing and fixing C.P. Angle valve 15mm dia.	3.00	Nos.	

	Providing and fixing C.P. Pillar cock 15mm dia. make of cera, hindware, jaguare	4.00	Nos.	
19.	Providing and fixing C.P. Floor Jali 100mm dia.	02.00	Nos	
20.	Providing and fixing C.P. over head brass shower arm 240mm long with wall flange (Jaguar ESSCO, Cera Hindware)	3.00	Nos	
21.	P/F Chlorinated polyvinyl chloride (CPVC) pipes 20mm dia. having thermal stability for hot and cold water supply, including all CPVC plain and brass threaded fittings, including fixing the pipe with clamps at 1 m spacing. this includes jointing of pipes and fitting with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in-charge. Internal work.	11.30	Rmt.	
22.	Providing and fixing P.V.C. Connection 600mm long.	10.00	Nos	
23.	S/f of G.I. Nipple 100mm long 15mm dia.	12.00	Nos	
24.	Providing and fixing C.P. Long body bib cock 15mm dia. make of plumber	2.00	Nos.	
25.	C.P. Brass Shop desk..	23.00	Nos.	
26.	P.V.C. water storage tank sintex are equivalent triple layer	1000.00	Ltr.	
27.	P/F of G.I. Long screw 25mm dia.	2.00	Nos.	
28.	P/F of G.I. Long screw 32mm dia.	2.00	Nos.	
29.	S/F of G.I. socket 15mm dia.	11.00	Nos	
30.	P/f of internal fittings for P.V.C cistern.	12.00	Nos.	
31.	Providing and fixing C.P. Brass spandle for basin mixer/wall mixer.	2.00	Nos	
32.	Providing Plumber with helper for repairing of old fittings	6.00	Nos	
33.	Providing labour for cleaning of site and collecting malwa.	3.00	Nos.	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours Faithfully

(Ram Velas Verma)
Executive Engineer

No. 2180-85/M/10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Chief Medical Superintendent, K.G.M.U, U.P. Lucknow
4. Dr. Richa khanna, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU, Website.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

(Ram Velas Verma)
Executive Engineer