

निर्माण विभाग

फोन (कुलसचिव कार्यालय): 0522-2257540 बेवसाइट: www.kgmu.org

त्रांकः ------ 841/191

QUOTATION NOTICE

	दिनांक:	
	201-1-	
-	2012120	11
	1 1100	7

To.		*
10,		
	M/s	

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge	58.68	Sqm	
2.	Drilling suitable holes upto and including 12mm dia in reinforced or plain cement concrete with power driven drill machine to a minimum depth of 100mm upto 200mm in RCC beams lintels coloums and slabs to introduce steel bars for sunsheds /balconies including fixing	12.00	Nos	
	the steel bars in posintion usig epoxy resin anchor grout of approved make but excluding the cost of reinforcent all complete. as per direction of E.I.		z.	٠
3	Mild steel work for reinfocement in plain cement cocncrete including binding bending and cutting complete.	14.88	Kg	
4	Fabrication of M.S structure with angle including labour material T&p complete.	17.85	Kg	
5	P/L 18mm thick cement plaster in two coats under layer 12mm thick cement plaster 1:5 on Ceiling with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	9.54	Sqm	ň.
6	P/L 12mm thick cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&P etc. for proper completion of work	47.42	Sqm	
7	P/L floor tiles in size 600x600mm with water absorption less then 0.08% and conferming to IS: 15622 of approved make in all colours and sheds, laid with cement based high polymer modified quick set tile adhesive (water based) in average 6mm thickness including grouting of joints etc. complete.	11.72	Sqm	
8	P/L 18mm thick black granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete.	2.97	Sqm	h
9	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete.	5.40	Sqm	d.
10	Applying one coat white cement on new surface.	58.68	Sqm	
11	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	58.68	Sqm	1
12	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	13.77	Sqm	×
13	Providing and laying white cement basede putty of average thickness 0.60mm of approved brand on old painted wall surface surface.	13.77	Sqm	





फोन (कुलसचिव कार्यालय) : 0522-2257540 बेवसाइट : www.kgmu.org

दिनांकः.... Distempering with oil bound distemper two coat of approved brand 14 old Surface to give an even shade including all material labour T&P 72,45 Sqm etc. complete. P/F ISI marled 30mm thick flush door shutter decorative type core of 15 block board constrction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or croos 1.94 Sqm bands and faces of shutters including ISI marked steel butt hinges with necessary fitings. P/F Stainless steel tower bolts with 10mm dia rod & Screw 200mm 16 01 No. P/F stainless steel door handle with Screw 150mm long. 17 02 Nos P/F stainless steel sliding bolt 16mm dia nuts & bolt 300mm 18 01 No. 19 Cartage for disposal of malwa up to 10km away from site. 2.70 Cum Providing labour for cleaning of site and collecting malwa. 20 02 Nos

Terms & Conditions.

- 1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
- 2. The work will be completed within given time.
- 3. Quantity can be increase or decrease as per requirements.
- 4. Conditional quotations are liable to be rejected.
- 5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Suresh Kumar)

Executive Engineer

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.

2. Faculty Incharge, Website Administratiion Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 261.02/24...Toc.1.1.0.8.1.20.24

Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow

Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow

Notice Board.

(Suresh Kumar) Executive Engineer