


**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW**

of dt. 30/10/19

Quotation Notice

Sub:- Misc Civil Brick, Red Lakha, Aluminium & other work, Nursing station (Counter) Casulty front Deptt. of Trauma Center, K.G.M.U. U.P., Lucknow



Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated..... 7-11-2019

Sl.No	Particular	Quantity	Unit	Rates
1	Class-150 Brick work 1:4 cement C-Sand in wall Superstructure below 12c.m. thick.	0.61	Cum	
2	R.C.C. Slab in 1:2:4 cement C-Sand stone aggregate.	0.25	Cum	
3	Mild Steel work 10/12mm dia as for reinforcement.	18.30	Kg	
4	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18mm thick stone slab over 20mm (average) thick base of cement mortar 1:4 (1 cement:4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-charge.(Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.)	3.09	Sqm	
5	S/f of S.S. Railing 304 grade 16 gauge with S.S balustrade of s.s. pipe and top rail 50mm dia including welding, grinding, polishing and height of railing 900mm.	5.20	Rmt	
6	S/F anodized aluminium door 2mm thick fully glazed made aluminium door tube size 83.50x44.65mm as vertical member 114.00x44.65mm with 5mm thick glass.	3.50	Sqm	
7	Providing and laying Vitrified tiles in floor with different sized(thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade laid with cement based high ploymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 6mm. thickness, including grouting of joints (Payment for grouting of joints to be made separately) (Size of tile 600x600mm)	7.20	Sqm	
8	P.L. Kajari or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheilded on 20mm. thick cement mortar in 1:4 cement and coarse sand including grouting of joints with white cement matching pigment.	6.60	Sqm	
9	P.L of 20mm. approved quality of Red Lakha granite slab/stone in rise of steps skirting dodo walls and pliiars, laid of 10mm. thick base jointed with cement slurry including colouring all labour material T & P etc. upto the proper competition of the work as per dircition of Engineer-in-charge.	4.12	Sqm	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation

Yours Faithfully

(Ram Velas Verma)
Executive Engineer

5374-79/M/10 Date 30/10/19

Copy for information and necessary action to:

1. Register, K.G.M.U, U.P Lucknow
2. Finance Officer, K.G.M.U, U.P Lucknow
3. Chief Medical Superintendent, Trauma Center, K.G.M.U, U.P Lucknow
4. Mr. Sanjay Bhattacharya, Website Administration Finance & Control, P.H.I Bhawan, K.G.M.U for uploading the quotation Notice in K.G.M.U.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P Lucknow
7. Notice Board.

(Ram Velas Verma)
Executive Engineer