



375

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग R. 19-10-2020

फोन : (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक

4658/M/10

QUOTATION NOTICE

दिनांक: 17/10/2020

To, M/s.....
.....
.....

The sealed quotations are invited for making of drain with M.S cover and other misc.work in front of Micro-biology department (old blood bank) from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 23/10/2020.....

Details of the work as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling cement concrete or granolithic floors including base concrete and including stacking of dismantled materials as directed by E/I.	14.55	Sqm.	
2.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	1.16	Cum.	
3.	M-150 class brick work 120mm thick in 1:4 cement, coarse sand in foundation including supply of all materials, labours and T&P etc. for proper completion.	9.66	Sqm.	
4.	Fabrication of M.S Structure with M.S angle and flat for drain.	485.00	Kg.	
5.	P/L 40mm thick cement concrete flooring with floating coat of neat cement in 1:2:4 cement, coarse sand 20mm stone grit.	8.25	Sqm.	
6.	P/L vitrified floor tiles in size 600x600mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	3.60	Sqm.	
7.	P/L 12mm cement plaster in 1:3 (1 Cement :3 Coarse sand) finished with a floating coat of neat cement.	12.60	Sqm.	
8.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.21	Cum.	
9.	S/F of C.I pipe including fitting 100mm dia. HEPCO make.	6.10	Rmt.	
10.	S/F C.I door bend 100mm dia.	01	No.	
11.	S/F C.P floor jali 100mm dia.	01	No.	
12.	S/F C.I Nahani trap 100mm dia HEPCO make.	01	No.	
13.	Providing sweeper with helper for cleaning of sewer and chambers.	02	Nos.	
14.	Cartage for disposal of malwa upto 10km away from the site.	2.81	Cum.	

46/ JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक

Terms & Conditions.

दिनांक:

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

No. 4659-63/M/16 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU Website from date 17/10/2020 To 23/10/2020
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer