



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

437/M10

QUOTATION NOTICE

दिनांक:

06/06/2024

To,

M/s.....

.....

The sealed quotations are invited for Repairing and painting of false ceiling in cath lab including other misc. work at IARI cardiology KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Registered contractors of kgmu may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 13/06/2024.

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	L/C for repairing of old damaged false ceiling including material, labour T&P complete.	7.56	Sqm.	
2.	P/L Vitrified wall tiles 600x600mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and shades, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment.	5.04	Sqm.	
3.	P/F float glass panes of 5mm thick in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per directions of E/I.	3.40	Sqm.	
4.	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	27.42	Sqm.	
5.	Repairing of old aluminium doors with 8mm dia. Fully threaded tie rod with nut and washer including placing on proper position in aluminium door frame.	8.88	Sqm.	
6.	P/F of S.S hinges 100mm long with stainless steel screws etc. complete.	12	Nos.	
7.	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of E/I.	17.49	Sqm.	
8.	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of E/I.	17.49	Sqm.	
9.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.14	Cum.	
10.	Fabrication of M.S frame for chambers including labour material t&p complete.	92.00	Kg.	
11.	P/L RCC work in covers 1:1.5:3 cement, coarse sand and stone aggregate.	0.45	Cum.	
12.	Mild steel work for reinforcement in plain cement concrete including binding, bending and cutting complete.	70.71	Kg.	
13.	Providing Carpenter with helper for repairing of old door/window.	04	Nos.	

11/07



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----


दिनांक:.....

14.	Providing labour for cleaning of site and collecting malwa.	08	Nos.	
-----	---	----	------	--

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully



(Suresh Kumar)
Executive Engineer


JE

No. 437/110 / of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 06/06/2024 To 13/06/2024
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


JE