



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग



फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 बेवसाइट : www.kgmcindia.edu.

पत्रांक: -----

5380/  
M-10

दिनांक: 31/10/19

**QUOTATION NOTICE**

To,

M/s.....

.....

.....

The sealed quotations are invited for Providing and Laying wall tiles and other misc. work at ground floor near entrance in Peadiatrics department from the registered contractor of KGMU. The detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated .....

Details of work as given below:-

S.L.No.	Particulars	Quantity	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	32.10	Sqm.	
2	P/L kajaria or equivalent wall tiles 300x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment etc complete.	28.09	Sqm.	
3	P/L vitrified floor tiles in 600x600mm (thickness to be specified by the manufacture ) with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	4.01	Sqm.	
4	Scraping old white or color wash including disposal of refuse as directed by engineer in charge.	25.37	Sqm.	
5	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, on old surface to prepare the surface even and smooth complete.	25.37	Sqm.	
6	Distemping with oil bound distemper two coat of approved brand old Surface to give an even shade including all material, labour T&Petc complete.	84.58	Sqm.	
7	Etching of kuta stone for cleaning of kuta stone flooring.	49.09	Sqm.	
8	Painting two coat with Superior synthetic enamel paint on old Surface including supply of labour material t&p etc. complete.	39.89	Sqm.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.


पत्रांक: -----

दिनांक:.....

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.


Yours faithfully

  
(Dinesh Kumar Raj)  
Executive Engineer

No. 5381-85/MU  
of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 31.10.19 To 28.11.19
3. Sri Anjani Kumar Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.

  
(Dinesh Kumar Raj)  
Executive Engineer