किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ–226003
कार्यालय अधिशासी अभियंता (विद्युत / यॉत्रिक)

पत्रांक 207/E.E(E/M) दिनाँक 19/05/2023

Urgent Quotation Notice

Sub: - Misc electrical work for various Department at KGMU Lucknow

Kindly submit your Quotation/Estimate for providing the following work in sealed envelope to the undersigned in the interest of patient care/institution within 3 days from the date of dispatch.

S.No.	Particulars	Qty.		Rate in each	Amount in Rs.
	Registrar office Driver Room				
1	Wiring point for light with 1.5mm single core copper wire. as per PS NO 131C+187A	02	Nos.		
2	S/F of exhaust fan point modular with 1.5mm single core copper wire. as per PS NO 137C+187A	01	Nos.		
3	S/F of 10 A Plug Point Modular with 1.5 mm single Core Cooper Wire. as per PS NO 134 C+187C	01	Nos.		
4	S/F of power plug with 20A/250V flush type Modular type switch & 5 pin 20A 250V universal modular socket. 1139A	01	Nos.		
5	S/F of 5 amp Switch	02	Nos.		
6	S/F of 5 amp Socket	02	Nos.		
7	S/F of 1 module regulator normal. As per PS NO 1203A	01	Nos		
8	S/W of submain 2 x 4 sqmm with multistrand single core copper wire. as per PS NO 216 C	03	Mtr.		
9	S/F of ceiling fan 1200 mm (Crompton/Bajaj/havells make)	01	Nos.		
10	S/F of 9 " fresh air fan	01	Nos.		
11	S/L of 2 x 10 sqmm PVC alluminium cable weather proof	18	Nos.		
12	S/F of 6 way SPN DB. As per PS No 1022A	01	Nos.		
13	S/F of 63 amp DP MCB as per PS No 1011	01	Nos.		
14	S/F of 6-32 amp MCB as per PS No 1002	04	Nos.		
	Pediatric Nicu Ward				
15	S/L of aluminium armoured cable 25 x 3.5 core as per PS No 501 J	44	Mtrs.		
16	S/F of gland 35 sqmm as per PS No 503 J	02	Nos.		
17	S/F of lug 25 sqmm as per PS NO 504 E	06	Nos.		
18	S/F of lug 16 sqmm as per PS No 504 D	02	Nos.		
19	S/F of 63 amp TP MCB as per PS No 1017	01	No.		
	I T cell Room No B				
20	S/F of 10 A Plug Point Modular with 1.5 mm single Core Cooper Wire as per PS No 134 C+187C	04	Nos.		
21	S/F of power plug with 20A/250V flush type Modular type switch & 5 pin 20A 250V universal modular socket. As per PS No 1139 A	04	Nos.		
22	S/W of submain 2 x 4 sqmm with multistrand single core copper wire. as per PS NO 216 C	32	Mtr.		
				Total	

Terms & Conditions:-

1. G.S.T. : As Applicable.
2. All the works shall be completed within the given time period as per work order.
3. Quantity can be increase or decrease as per requirements.
4. All the works shall be carried out as per PWD specifications.
5. Firm should fill the A.R. Rate other than schedule Rate.
6. Contractor having experience in electrical department KGMU Lucknow can quote their rates.

Your Faithfully

Executive Engineer (Electrical)
K.G.M.U.U.P., LUCKNOW

No.....of DT.....

Copy for information and necessary action to:-

1. Dr. Richa Khanna, Faculty In charge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from.....
2. Notice board.

Executive Engineer (Electrical)
K.G.M.U.U.P., LUCKNOW