



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

4376/910

दिनांक 27/09/18

QUOTATION NOTICE

The sealed quotation are invited for Construction of toilet for Guest Room at T.G. Hostel KGMU from the registered contractor of KGMU the detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated 27/09/18
Detail of the works as given below-

Sl.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling brick work or stone work in lime or cement mortar and including stacking of materials as directed by the engineer incharge.	0.88	Cum	
2.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	12.86	Sqm	
3.	Earth work in excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom.	4.56	Cum	
4.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	1.24	Cum	
5.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.70	Cum	
6.	P/L RCC Lintel in 1:2:4 cement, coarse sand & 20mm stone grit.	0.02	Cum	
7.	P/L RCC Plat form in 1:2:4 cement, coarse sand & 20mm stone grit.	0.14	Cum	
8.	Mild steel work for reinforcement in plain cement concrete.	12.86	Kg	
9.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	20.37	Sqm	
10.	P/L PCC 1:6:12 cement, fine sand& 40mm brick ballast.	0.67	Cum	
11	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.50	Cum	



किंग जार्ज चिकित्सा विश्वविद्यालय २०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलासचिव कार्यालय) : 0522-2257540 फेक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक:

दिनांक:

12	P/L kajaria or equivalent floor tiles 300x300mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment	2.51	Sqm	
13	P/L vitrified floor tiles in different sizes (thickness to be specified by the manufacture) with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	2.75	Sqm	
14	P/L kajaria or equivalent Vitrified wall tiles 300x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	11.20	Sqm	
15	20mm thick cement plaster 1:4 cement cement coarse sand backing coat 17mm finishing coat 3mm complete.	2.76	sqm	
16	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	20.37	Sqm	
17	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	20.00	Sqm	
18	Distempering with oil bound distemper two coat of approved brand on old Surface to give an even shade including all material , labour T&P etc. complete.	65.79	Sqm	
19	Application of two coats Ultima apex paint on outer surface of wall including supply of all materials, labours and T&P etc.for proper completion of the work.	5.90	Sqm	
20	S/f of Descon make or equivalent Solid PVC door frames of 65mm x 46mm & shutter 25mm (Solid thick with ribs) Grey/Dark Grey/Black thick mode of Foam PVC sheet including Aluminum hardware, sliding bolt, Handles & hinges.	1.76	Sqm	
21	Cartage for disposal of malwa from site.	5.18	Cum	
22	Labour charges for cleaning and other misc. work.	4.00	Nos	
23	S/F GI pipe 15mm dia with fittings 'B' class	40.50	Rmt	
24	S/F PVC pipe 100mm dia.	4.50	Rmt	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----


दिनांक:

25	S/F 10 Lit PVC low down cistern of appd. Quality with internal fitting complete.	1.00	Nos	
26	S/F white glazed European seat.	1.00	Nos	
27	S/F of C.P health Faucet with lead 1.5 meter of appd. Quality	1.00	Nos	
28	S/F wash hand basin white glazed 22"x16" complete with pillar cock, bracket, waste jali, waste pipe, PVC connection etc	1.00	Nos	
29	S/f looking mirror glass of appd. Quality.	1.00	Nos	
30	S/F C.P bross towel rod 720x20mm	1.00	Nos	
31	S/f C.P soap dish of appd. Quality.	1.00	Nos	

Term & Condition

1. C.S.T & Labour cess shall be applicable as per rules.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.


Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

4377-81/M-10
No. of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 22/09/18
To: u. i. a. / 18...
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadv, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer

