

(P: 20-10-2020)  
**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY**  
**U.P., LUCKNOW**

402

No. 4717/M/10

of dt. 19/10/2020

Quotation Notice

Misc Civil Toilet work 2nd Floor Gynic O.T. at R.A.L.C., K.G.M.U., U.P., Lucknow

Dear Sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 27/10/2020


Sl.No	Particular	Quantity	Unit	Rates
1	Dismantling of old unserviceable flooring/Kota stone	8.94	Sqm	
2	M-150 class 120mm thick brick work in 1:3 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	0.64	Sqm	
3	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300mm or more (thickness to be specified by the manufacture), of 1st quality conforming to IS: 15622, of approved make, in colours white, Ivory, Grey, Fume Red Brown, laid on 20mm thick cement mortar 1:4 sqm including grouting the joints with white cement and matching pigments etc complete.	9.50	Sqm	
4	P.V.C. Pipe 110mm dia ISI make.	12.80	Rmt	
5	Providing and fixing G.I. Pipe 15mm dia with fitting 'B' class.	8.05	Rmt	
6	Providing and fixing C.P. Angle valve 15mm dia.	03	No	
7	Providing and fixing Two way bib cock heavy quality short body with wall flang (Jaguar, ESSCO, Cera, Hindware.)	01	No	
8	Providing and fixing Commord sheet with cover.	01	No	
9	Providing and fixing 10 Lit P.V.C. Low down cistern for appd. Quality in completed.	02	No	
10	Providing and fixing P.V.C. Connection 600mm long.	06	No	
11	Providing and fixing C.I. Nahani Trap 100mm dia.	01	No	
12	Providing and fixing P.V.C. Socket 100mm dia.	04	No	
13	Providing and fixing Bend 100mm dia.	05	No	
14	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	3.24	Sqm	
15	Providing and fixing C.P. over head brass shower arm 240mm long with wall flange (Jaguar ESSCO, Cera Hindware)	01	No	
16	Providing and fixing C.P. Zet spray with C.P. lead 1.5 meter for appd. quality.	01	No	
17	Providing & laying water proofing treatment by applying cement slurry mixed with water proofing cement compound consisting of applying in two layers including preparation of surface, treatment & sealing of all joints, corners complete.	8.94	Sqm	
18	Providing and fixing C.I. Plain Band 100mm dia.	06	No	
19	Providing and fixing C.P. Long body bib cock 15mm dia. make of plumber	05	No	
20	Providing and fixing C.P. Pillar cock 15mm dia.	06	No	
21	Replace of C.P. short body bib cock 15mm dia make of plumber.	07	No	
22	40mm thick flooring 1:2:4 cement C-sand stone Aggregate of with floating coat of neat cement.	0.72	Sqm	
23	Providing and fixing Plain glass 5mm thick with wooden beading.	1.60	Sqm	
24	Providing and fixing Hepco red HC.I pipe including fitting 100mm dia.	13.10	Rmt	
25	Providing and fixing Wash hand basin white glazed 22x16 complete with pillar cock, bracket, waste jali, waste pipe, P.V.C. connection etc.	02	No	
26	Providing and fixing C.P. waste jali 100mm dia. for wash basin.	01	No	
27	Providing and fixing of P.V.C. waste pipe 32mm for wash basin/sink	02	No	
28	S/f of Bracket for flushing cistern/sink and wash hand basin.	02	Pair	

**Terms & Condition**

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.

1. The work will completed within given time in the work order.
2. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully


  
(Ram Velas Verma)  
Execcutive Engineer

No. 4718-23/M/10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Medical Superintendent., R.A.L.C., K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for uploading the quotation  
Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

  
(Ram Velas Verma)  
Execcutive Engineer