



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

दिनांक: 27/07/21

क्र.क:

10/2 M-10/2021

### QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited for Providing and laying R.C.C. slab, floor tiles and painting of bag room at entrance of central library building. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 03/08/2021.

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling old tile including disposal of refuse as directed by Engineer-in-charge.	5.68	Sqm.	
2.	Dismantling existing old plaster including disposal of dismantled as directed by engineer incharge.	5.80	Sqm.	
3.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	22.40	Sqm.	
4.	Centering and shuttering including struting, propping etc. and removal of form for roofs etc complete	5.69	Sqm.	
5.	Drilling suitable holes upto and including 12mm dia in reinforced or plain cement concrete with power driven drill machine to a minimum depth of 100mm upto 200mm in RCC beams, lintels, columns and slabs to introduce steel bars for sunshades/ balconies including fixing the steel bars in position using epoxy resin anchor grout of approved make but excluding the cost of reinforcement, all complete as per direction of E/I.	180	Nos.	
6.	Mild steel work for reinforcement in plain cement concrete including binding,bending and cutting complete.	93.42	Kg.	
7.	P/L RCC work in slab 1:1.5:3 cement, coarse sand and stone aggregate.	0.68	Cum.	
8.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	12.50	Sqm.	
9.	P/L vitrified floor tiles in 600x600mm (thickness to be specified by the manufacture ) with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and shades , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	13.41	Sqm.	
10.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	12.50	Sqm.	

Ms. R. K. Singh

Sur

11.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	22.40	Sqm.	
12.	Distemping with oil bound distemper two coat of approved brand on old Surface togive an even shade including all material , labour T&P etc. complete.	54.50	Sqm.	
13.	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	4.73	Sqm.	
14.	Fabrication of M.S structure for gate etc. including all materials labour complete.	186.80	Kg.	
15.	Painting 2 coats with supirior synthetic enamel paint on new surface with one coat primer upto 10 cm width or grith.	40.58	Sqm.	
16.	Providing labour for cleaning of site and collecting malwa.	04	Nos.	
17.	Cartage for disposal of malwa up to 10km away from site.	1.90	Cum.	

Terms & Conditions


1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

7013-7017/M-10/2021


  
 (Dinesh Kumar Raj)  
 Executive Engineer

No...../ of DT. As Above

  
 JE  
  
 AE

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 27/07/2021 To 23/08/2021
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.

  
 (Dinesh Kumar Raj)  
 Executive Engineer