




किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.



पत्रांक: 5798/M-10

दिनांक: 25/11/19

**QUOTATION NOTICE**

To,  
M/s.....  
.....  
.....

The sealed quotations are invited for Repairing and painting work of Outer portion of Sanjha Chulha KGMU from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 02/12/19

Details of work as given below:-

S.I.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling of old door / windows chauhats with hold fast & including stacking of dismantled material directed by the engineer incharge.	3.21	Sqm.	
2.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	26.12	Sqm.	
3.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	18.92	Sqm.	
4.	P/L 12mm cement plaster in 1:4 cement,coarse sand finished with floating coat of neat cement.	15.02	Sqm.	
5.	S/f of Solid PVC door frames of 65mm x 46mm & shutter 25mm (Solid thick with ribs) Grey/Dark Grey/Black thick mode of Foam PVC sheet including Aluminum hardware, sliding bolt, Handles & hinges.	3.21	Sqm.	
6.	Applying one coat of water thinnable cement primer of approved brand on new plastered wall surface.	18.43	Sqm.	
7.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	201.88	Sqm.	
8.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	18.92	Sqm.	
9.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	192.00	Sqm.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: .....

दिनांक: .....

10.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	220.31	Sqm.	
11.	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	18.29	Sqm.	
12.	S/F of PVC pipe of 75mm dia.	0.60	Rmt.	
13.	S/F of PVC pipe of 110mm dia.	4.30	Rmt.	
14.	Providing labour for cleaning of roof and collecting malwa.	4	Nos.	
15.	Cartage for disposal of malwa up to 10km away from site.	3.13	Cum.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)  
Executive Engineer

No. 5799-5803/M-10  
of DT.

Copy for information and necessary action to:-

16. Registrar, King George's Medical University U.P, Lucknow.
17. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 29/11/19  
To 22/11/19
18. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
19. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
20. Notice Board.

(Dinesh Kumar Raj)  
Executive Engineer