

WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY  
U.P, LUCKNOW

No. 5006/MK10

of dt. 09/10/19

Quotation Notice

**Sub:-** Misc Civil Brick, Plaster, Reserve Faculty Basement Parking Front wall & G.I. Sheet (Shed) work & other work Mattern office Back side, Deptt. of Main Building.



Dear sir,


Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated. 16/10/19



Sl.No	Particular	Quantity	Unit	Rates
1	Class-150 Brick work 230mm thick wall in 1:4 cement and coarse sand in superstructure.	3.90	Cum	
2	P/L R.C.C. Beam in 1:1½:3 cement, coarse sand and 20mm stone grit.	1.08	Cum	
3	Mild Steel work 10/12mm dia as for reinforcement.	82.57	Kg	
4	12mm. thick plaster 1:3 cement C-Sand in wall.	15.17	Sqm	
5	P/L of Birla white putty for making good smooth surface.	15.17	Sqm	
6	Application of two coats Apex. Ultima paint of Approved Brand on old Surface Given an even Shade including supply of all material, labour T&P as required for proper completion of work	15.17	Sqm	
7	Providing and fixing pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50mm (+0.05%) total coated thickness with zinc coating 120 grams per sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	62.49	Sqm	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation

Yours Faithfully

  
(Ram Velas Verma)  
Executive Engineer


 

No. 5007-12/MK10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Chief Medical Superintendent, K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

  
(Ram Velas Verma)  
Executive Engineer

