



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 564/M/10

दिनांक 04/05/18

**QUOTATION NOTICE**

To,

M/s.....

The sealed quotation are invited for Repair and PCC floor work for Underground water tank Near ICTC building/ Pathology Deptt. KGMU Campus.KGMU as given below. The detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated 11/05/18

Sl.No.	Particulars	Quantity	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	35.50	Sqm	
2	Class 150 brick work 230mm thick in 1; 4 cement coarse sand in walls for superstructure.	1.40	Cum	
3	P/L of 1:6:12 cement fine sand brick aggregate	7.60	Cum	
4	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	35.50	Sqm	
5	P/L one coat of water proof cement paint of approved quality on new surface.	35.50	Sqm	
6	40mm thickness flooring 1:2:4 cement coarse sand stone aggregate of with floating coat of neat cement.	95.00	Sqm	
7	20mm thick cement plaster 1:4 cement cement coarse sand backing coat 17mm finishing coat 3mm complete.	2.00	Sqm	
8	P/L C.C work 1:2:4 cement coarse sand stone aggregate	0.85	Cum	
9	Application of two coats Ultima apex paint on outer surface of wall including supply of all materials, labours and T&P etc.for proper completion of the work.	35.50	Sqm	
10	Fabriacation of MS grill /railing with welding machine including all labour material T&P etc. complete.	30.00	Kg	
11	Labour charges for cleanig of malwa.	15.00	Nos	

**Term & Condition**

1. G.S.T shall be applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.

Yours faithfully

(Dinesh Kumar Raj)  
Executive Engineer