

(Civil Section)
King George's Medical University Uttar Pradesh,
Lucknow..

No. 6689/M70

of date 28/11/2020

Quotation Notice

Sub:- Construction of boundary wall and other Misc. Civil work front of Oxygen Gas plant I.D.H
 Campus at K.G.M.U. Lucknow.

Dear sir,


Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 24/11/2021



Sl.No	Particular	Quantity	Unit	Rates
1.	M-150 class 120mm thick brick work in 1:3 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	18.69	Sqm	
2.	Class-150 Brick work 23cm thick wall in 1:4 cement and coarse sand in superstructure.	1.68	Cum	
3.	P/L in position ready Mixed cement concrete of specified grade fully automatic batching plant and Transport of site of work in Transit mixture for all leads Having Continuous agita full on ixcerment factual as per mixed sign of plain cement concrete work / including pumping of R.M.C from transit mixer to site of laying and curing Excluding the cost of Centering shuttering & finishing IS: 9103 to accieractual Rela front setting of concrete complete etc. CM-15 1:2:4 Grade cement concrete.	3.63	Cum	
4.	12mm thick plaster 1:4 cement C-Sand in wall.	52.17	Sqm	
5.	Mild Steel or iron work in heavy sizes such as trusses; builds up gates, door frames, record racks, roof work, gates etc; wrought to required form including drilling holes, revetting or welding where necessary and also including supply of steel, bolts, nuts etc. & their fixing required for proper completion of the work.	78.40	Kg	

Terms & Condition

1. Rates quoted should be inclusive all taxes.
2. The work will completed within one week from the date of order.

Yours Faithfully


 (Ram Velas Verma)
 Executive Engineer

No.

6690-95/M-10

Date.

28/12/2021

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Chief Medical Superintendent of K.G.M.U, U.P. Lucknow
4. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
5. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Dr. Sandeep Bhattacharya, Faculty Incharge, Web Site, Data center P.H.I.
Building of K.G.M.U, U.P. Lucknow
7. Notice Board



(Ram Velas Verma)
Executive Engineer

